

# Carey Precast Concrete



#### Pre-Installation Requirements:

1. Provide truck access to within 10' of the center of the PermEntry unit.

The Complete Basement Entrance

- 2. Foundation footing and opening should be LEVEL, PLUMB and SQUARE.
- Width of opening in foundation wall should be 40" maximum for all sizes.
- 4. Ensure proper soil drainage at base of unit. A footing drain to daylight is recommended.
- When foundation is backfilled, leave minimum work area for PermEntry installation as shown.
- 6. Basement floor or equivalent slab should be poured in the concrete wall.
- Hold foundation tar coating back minimum 12" each side of opening.


#### How to Measure:


- 1. Determine the measurement from the finished grade to the foundation footing.
- Refer to table below to select proper size. Top of casting should be a minimum of 2" above finished grade.
- Double check your pre-installation requirements and check site to determine that there is proper truck access to and from the PermEntry installation site.


#### Post-Installation Requirements:

- Properly backfill and compact excavation with clean, suitable fill and/or stone. NEVER USE CONSTRUCTION DEBRIS and NEVER backfill higher than 2" below top of concrete casting.
- Final grade should be adjusted to leave 2"-6" of casting above finished grade, immediately slope grade away from the PermEntry unit in all directions.
- 3. Avoid locating down spouts or sump discharge near the PermEntry unit.
- 4. An insulated door at bottom of stairs is recommended to reduce heat loss.
- A finish coat of acrylic latex in white or light color must be applied to all interior and exterior steel surfaces within forty-five (45) days of installation. Note: Bilco does not recommend the use of Rust Oleum products.

#### Job Requirements








#### PermEntry Size Footing to Grade 35" - 41" S 0 52" - 58" 59″ - 66″ В C\* 67" - 74" D\* 75" - 82" E\* 83" - 91" F\* 92" - 99"

#### How to Order

Licensed Dealer



Carey Precast Concrete

\* Optional Ultra Series Door available for sizes C, D, E and F only.

55-1/2"

58

58



An optional basement door keyed lock kit is available for added home security.

#### Carey Precast 3436 Township HWY 98 Carey, OH 43316 800-852-3987 www.careyprecast.com

Imagine... What Bilco can do for your basements (800) 854-9724 • www.bilco.com

<u>Rilco</u>

#### Copyright 2010 The Bilco Company. All rights reserved.

Printed in the U.S.A P-10 10.R1

#### A PermEntry<sup>®</sup> Unit for Every Home

### **Precast Steps**

#### Step Sizes:

Each step is 7" high 1 Step = 7" High 2 Steps = 14" High 3 Steps = 21" High 4 Steps = 28" High 5 Steps = 35" High 6 Steps = 42" High

Widths Available: 4 ft. wide 5 ft. wide 6 ft. wide

Landings Available: No Landing 24" Landing 48" Landing NOTE: Landing is the top step

# Carey Precast Concrete

#### Carey, OH (800) 852-3987 www.careyprecast.com





Precast concrete Steps are designed for appearance and strength to enhance residential and commercials structures.

Precast Concrete Steps eliminate the need for painting and replacing deteriorating lumber.

Risers are low enough for children and the elderly and tread depth is comfortable for all.

Installation is a simple matter of lowering the step into place and leveling the unit. Units should be installed on a poured in place concrete pad or with flat concrete blocks under each corner on compacted sand or gravel fill.

NOTICE: Carey Precast Concrete is not responsible for damage caused by the application by others of harmful salts, chemicals, ashes or any other material to the surfaces of the steps.

## **Septic Tanks**

Tanks Available: 2 compartment septic tanks Dosing tanks, pumps, controls Distribution boxes, pipe, fittings

Also Available: Singulair Aeration Singulair NPDES Singulair Green Aeration and NPDES



Septic Tank Sizing:

1000 Gallon Septic Tank: 72" Height

## Carey Precast Concrete

Carey, OH (800) 852-3987 www.careyprecast.com

All Tanks are ODH Certified for Structural and Watertight Assurance.

1000 Gallon Septic Tanks 1500 Gallon Septic Tanks 2000 Gallon Septic Tanks

Capacity is calculated below the flow line for true capacity

All Tanks come equipped with:

4" High pressure boot seals with clamps at the outlet & inlet
4" T-baffle at inlet
6" Outlet filter with 4" connection
20" Plastic risers with lid and concrete insert


82" Length 66" Width 60" To Bottom of inlet 56" To Bottom of outlet

1500 Gallon Septic Tank 59" Height 159" Length 72" Width 46" To Bottom of inlet 44" To Bottom of outlet

2000 Gallon Septic Tank 72" Height 159" Length 72" Width 59" To Bottom of inlet 57" To Bottom of outlet

#### All Tanks are Fully Reinforced





#### Inlet

Untreated wastewater enters the system here.

#### Pretreatment Chamber

Wastewater enters at the Singulair inlet and is equalized here as anaerobic bacteria and gravity precondition it.

#### **Aeration Chamber**

Here, safe, living aerobic bacteria convert the wastewater into stable substances. Flow equalization maximizes this biological oxidation and assures 24-hour retention and treatment.

#### Aerator provides complete treatment

Our exclusive aerator infuses the fresh air that safe, living microorganisms require to fully digest and treat wastewater inside the Aeration Chamber. Powered by our 1725 RPM, 115 volt, fractional horsepower motor, our quiet, reliable aerator is inexpensive to operate, reduces heat build up and dramatically increases bearing life. Each aerator is precision engineered, tested and certified to operate only 30-minutes per hour. Only the stainless steel aspirator shaft and reinforced nylon aspirator come in contact with liquid in the Aeration Chamber.

#### **Clarification Chamber**

Flow equalization enhances the settling of biologically active substances inside the Clarification Chamber. Wastewater has now been converted into clarified liquids in this chamber.

#### Flow Equalization Ports

They control the flow through all upstream and downstream processes and they regulate the amount of treated effluent that can enter the Bio-Kinetic System.

### Carey Precast Concrete

Carey Precast 3436 Township HWY 98 Carey, OH 43316 800-852-3987 www.careyprecast.com

#### **Bio-Kinetic**<sup>®</sup> System

Constructed entirely of plastic and rubber components that are impervious to this environment, our Bio-Kinetic System combines filtration, settling, non-mechanical flow equalization, optional disinfection, adjustable outlet weir and optional dechlorination features into a single, revolutionary package.

#### Precast Concrete Tank

Every Singulair System is constructed of high quality, non-corrosive materials under our rigid quality control standards. The tank, access risers and cover are reinforced precast concrete manufactured locally by your factory-trained, licensed Norweco distributor.

#### Inspection Cover

Access is safe and easy.

#### Outlet

Only a clear, safe and odorless liquid exits the system here for return to your environment.


#### SERVICE PRO' Control Center

EVERY SINGULAIR AERATOR IS INSTALLED WITH A SOLID STATE ELECTRICAL CONTROL CENTER. EACH IS EQUIPPED WITH RESETTABLE CURRENT SENSOR, ON/OFF SELECTOR SWITCH, RED WARNING LIGHT, TIME CLOCK, AUDIBLE ALARM, AUXILIARY INPUTS AND FCC LICENSED AUTODIALER FOR REMOTE MONITORING OF INDIVIDUAL COMPONENTS.

### **Catch Basins**

# Carey Precast Concrete

Carey, OH (800) 852-3987 www.careyprecast.com



18" x 18" Catch Basin

Inside dimensions: 18 x 18 x 30 2' x 2' Catch Basin

#### Flat risers available by special order

#### 3 x 3 Catch Basins

#### Inside Dimensions: 36 x 36 x48

#### Flat Risers available by special order

Inside Dimensions: 24 x 24 x 36

Risers available: 4", 6", 12", 24" Flat 4", 6", 12" Slant

Iron grates available All prices FOB Carey OH All prices subject to change without notice

ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE


### **Cattle Products**

# Carey Precast Concrete

Carey, OH (800) 852-3987 www.careyprecast.com

#### **Fenceline Feedbunks**

8' Standard Length 22" Front - 30" Back - 36" Wide 2400 lbs per section 3.5 cu ft. of feed per foot of bunk capacity 2 centered 5/8 threaded bolt inserts Fully reinforced Right or Left ends available






#### H-Bunks

26" tall - 10" deep trough 4000 lbs per section 3 centered bolt holes

#### Fully reinforced End plate with bolts available

#### Cattleguard

Dimensions: 16' long, 24" wide, 12" deep 2500 lbs per section Fully Reinforced Easy to install: Installs directly on the ground or conveniently over a pit Easy to clean: Each section can be removed to clean underneath.



#### ALL PRICES SUBJUCT TO CHANGE WITHOUT NOTICE.

# Carey Precast Concrete

#### Carey, OH (800) 852-3987 www.careyprecast.com

### Hog Slats

All Slats are hand trowled and have 1" spacing. Grade 60 rebar top and bottom

**Hog Products** 

S	iz	e	s	:	
-		-	-	-	

Sizes:			
Length	Width	Depth	Weight
10'	8"	5"	300 lbs
10'	6"	5"	250 lbs
8'	8"	4"	200 lbs
8'	6"	4"	175 lbs
6'	8"	4"	150 lbs
6'	6"	4"	110 lbs.
5'	5"	3.5"	75 lbs.
4'	5"	3.5"	60 lbs
Custom	lengths av	ailable.	



#### Support Beams

#### **Pen Dividers**

Standard Length: 10' Dimensions: 8" x 8" Grade 60 steel rebar Weight: 70 lbs per foot Custom Lengths Availabe



Lengths to 6' Height: 37" Base: 14" Top: 3" Weight: 200 lbs per foot




#### ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE.

### **Fuel Containment**

# Carey Precast Concrete

Carey, OH (800) 852-3987 www.careyprecast.com



#### **500 Gallon Containment**

#### **1000 Gallon Containment**

Cover not included

**Cover not included** 

Inside: 6' x 8', 30" deep

Outside: 6'6" x 8'6", 34" deep

Inside: 6' x 13'2", 30" deep

Outside: 6'6" x 13'8", 34" deep


#### Fully reinforced Bolt inserts cast in corners for tie downs Fuel tanks not included

Cover not included Plastic cover available at an additonal charge

ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE.

# Carey Precast Concrete

#### Carey, OH (800) 852-3987 www.careyprecast.com



**T-Walls** 

#### **T-Walls**

Single Component T-Wall design for fast installation and completion Each section is 8'6" tall, 5' long, 5' wide at base Tongue and groove design Sections bolt together Fully reinforced 5000 lbs per section Floor, roofing or covers not included





#### **T-Wall Dividers**

Featuring a single component design for fast installation and completion

6' tall - 8' long - 32" wide at base Tongue and groove design Fully reinforced 5000 lbs per section Tongue and groove design




ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE.

### **V-Blocks**

# Carey Precast Concrete

Carey, OH (800) 852-3987 www.careyprecast.com





#### **Standard Sizes Available:**

2' x 4' x 2'	Weight:	2400 lbs.
2' x 2' x 2'	Weight:	1200 lbs.
6' Cap x 26" x 6"	Weight:	900 lbs.

Stone Faced Step 30" deep x 48" Wide

**Blocks available Stone Face or Plain** 

ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE